


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT <input type="checkbox"/>				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER GMBU 104-32-8-17				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT MONUMENT BUTTE				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcozner@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU-74869			11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL	FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN			
LOCATION AT SURFACE	794 FSL 813 FWL		SWSW	29	8.0 S	17.0 E	S			
Top of Uppermost Producing Zone	173 FSL 686 FWL		SWSW	29	8.0 S	17.0 E	S			
At Total Depth	322 FNL 567 FWL		NWNW	32	8.0 S	17.0 E	S			
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 322		23. NUMBER OF ACRES IN DRILLING UNIT 10					
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 292		26. PROPOSED DEPTH MD: 6409 TVD: 6290					
27. ELEVATION - GROUND LEVEL 5241			28. BOND NUMBER WYB000493		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478					
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Surf	12.25	8.625	0 - 300	24.0	J-55 ST&C	8.3	Class G	138	1.17	15.8
Prod	7.875	5.5	0 - 6409	15.5	J-55 LT&C	8.3	Premium Lite High Strength	305	3.26	11.0
							50/50 Poz	363	1.24	14.3
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Heather Calder				TITLE Production Technician			PHONE 435 646-4936			
SIGNATURE				DATE 11/19/2014			EMAIL hcalder@newfield.com			
API NUMBER ASSIGNED 43013532340000				APPROVAL  Permit Manager						

NEWFIELD PRODUCTION COMPANY
GMBU 104-32-8-17
AT SURFACE: SW/SW SECTION 29, T8S R17E
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0' – 1,643'	
Green River	1,643'	
Wasatch	6,439'	
Proposed TD	6,409'(MD)	6,290' (TVD)

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1,643' – 6,439'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM**

a. Casing Design: GMBU 104-32-8-17

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	300'	24.0	J-55	STC	2,950 17.53	1,370 14.35	244,000 33.89
Prod casing 5-1/2"	0'	6,409'	15.5	J-55	LTC	4,810 2.36	4,040 1.98	217,000 2.18

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: GMBU 104-32-8-17

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft ³ /sk)
			ft ³			
Surface casing	300'	Class G w/ 2% CaCl	138 161	30%	15.8	1.17
Prod casing Lead	4,409'	Prem Lite II w/ 10% gel + 3% KCl	305 993	30%	11.0	3.26
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363 451	30%	14.3	1.24

*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 300 feet will be drilled with an air/mist system. The air rig is equipped with a 6 1/2" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ± 300 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.


9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated


bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the second quarter of 2014, and take approximately seven (7) days from spud to rig release.


T8S, R17E, S.L.B.&M.**NEWFIELD EXPLORATION COMPANY**

WELL LOCATION, 104-32-8-17,
LOCATED AS SHOWN IN THE SW 1/4
SW 1/4 (LOT 1) OF SECTION 29, T8S,
R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.
3. The Bottom of Hole bears S11°32'25"W 1143.11' from the Top of Hole.

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST
OF MY KNOWLEDGE AND BELIEF.



BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction.
LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28"
(Tristate Aluminum Cap) Elev. 5281.57'

NAD 83 (SURFACE LOCATION)
LATITUDE = 40°05'01.85"
LONGITUDE = 110°02'13.01"
NAD 27 (SURFACE LOCATION)
LATITUDE = 40°05'01.98"
LONGITUDE = 110°02'10.47"

TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 09-04-14	SURVEYED BY: S.H.	VERSION:
DATE DRAWN: 09-08-14	DRAWN BY: F.T.M.	V2
REVISED: 10-14-14 F.T.M.	SCALE: 1" = 1000'	

RECEIVED: November 19, 2014

NAD 83 (CENTER OF PATTERN)	NAD 83 (BOTTOM HOLE LOCATION)
LATITUDE = 40°04'53.31"	LATITUDE = 40°04'50.82"
LONGITUDE = 110°02'15.47"	LONGITUDE = 110°02'16.19"
NAD 27 (CENTER OF PATTERN)	NAD 27 (BOTTOM HOLE LOCATION)
LATITUDE = 40°04'53.45"	LATITUDE = 40°04'50.96"
LONGITUDE = 110°02'12.93"	LONGITUDE = 110°02'13.65"

RECEIVED: November 19, 2014



○—○ Existing Road



Tri State
Land Surveying, Inc.

P: (435) 781-2501
F: (435) 781-2518




**Existing 13-29-8-17 Pad
Proposed Well: 104-32-8-17
Sec. 29, T8S, R17E, S.L.B.&M.
Duchesne County, UT.**

DRAWN BY:	A.P.C.	REVISED:	10-14-14 A.P.C.	VERSION:
DATE:	09-10-2014			V2
SCALE:	1:100,000			

TOPOGRAPHIC MAP

SHEET

A



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY


Existing 13-29-8-17 Pad
Proposed Well: 104-32-8-17
Sec. 29, T8S, R17E, S.L.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED:	10-14-14 A.P.C.	VERSION:
DATE:	09-10-2014			V2
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET

B

Proposed Pipeline Map**Legend**

Existing Road

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

Existing 13-29-8-17 Pad
Proposed Well: 104-32-8-17
Sec. 29, T8S, R17E, S.L.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED: 10-14-14 A.P.C.	VERSION:
DATE:	09-10-2014		
SCALE:	1" = 2,000'		V2


TOPOGRAPHIC MAP

SHEET

C

Exhibit "B" Map

Existing 13-29-8-17 Pad
Proposed Well: 104-32-8-17

**Legend**

- 1 Mile Radius
● Pad Location

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

Existing 13-29-8-17 Pad
Proposed Well: 104-32-8-17
Sec. 29, T8S, R17E, S.L.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED:	10-14-14 A.P.C.	VERSION:
DATE:	09-10-2014			
SCALE:	1" = 2,000'			V2

TOPOGRAPHIC MAP

SHEET

D

Coordinate Report

Well Number	Feature Type	Latitude (NAD 83) (DMS)	Longitude (NAD 83) (DMS)
13-29-8-17	Surface Hole	40° 05' 01.67" N	110° 02' 13.16" W
104-32-8-17	Surface Hole	40° 05' 01.85" N	110° 02' 13.01" W
104-32-8-17	Center of Pattern	40° 04' 53.31" N	110° 02' 15.47" W
104-32-8-17	Bottom of Hole	40° 04' 50.82" N	110° 02' 16.19" W
Well Number	Feature Type	Latitude (NAD 83) (DD)	Longitude (NAD 83) (DD)
13-29-8-17	Surface Hole	40.083797	110.036988
104-32-8-17	Surface Hole	40.083847	110.036948
104-32-8-17	Center of Pattern	40.081476	110.037631
104-32-8-17	Bottom of Hole	40.080784	110.037830
Well Number	Feature Type	Northing (NAD 83) (UTM Meters)	Longitude (NAD 83) (UTM Meters)
13-29-8-17	Surface Hole	4437502.281	582102.510
104-32-8-17	Surface Hole	4437507.787	582105.893
104-32-8-17	Center of Pattern	4437244.043	582050.519
104-32-8-17	Bottom of Hole	4437166.998	582034.343
Well Number	Feature Type	Latitude (NAD 27) (DMS)	Longitude (NAD 27) (DMS)
13-29-8-17	Surface Hole	40° 05' 01.81" N	110° 02' 10.62" W
104-32-8-17	Surface Hole	40° 05' 01.98" N	110° 02' 10.47" W
104-32-8-17	Center of Pattern	40° 04' 53.45" N	110° 02' 12.93" W
104-32-8-17	Bottom of Hole	40° 04' 50.96" N	110° 02' 13.65" W
Well Number	Feature Type	Latitude (NAD 27) (DD)	Longitude (NAD 27) (DD)
13-29-8-17	Surface Hole	40.083835	110.036283
104-32-8-17	Surface Hole	40.083885	110.036242
104-32-8-17	Center of Pattern	40.081514	110.036925
104-32-8-17	Bottom of Hole	40.080822	110.037125
Well Number	Feature Type	Northing (NAD 27) (UTM Meters)	Longitude (NAD 27) (UTM Meters)
13-29-8-17	Surface Hole	4437296.957	582164.761
104-32-8-17	Surface Hole	4437302.463	582168.144
104-32-8-17	Center of Pattern	4437038.720	582112.771
104-32-8-17	Bottom of Hole	4436961.674	582096.596



P: (435) 781-2501
F: (435) 781-2518

NEWFIELD EXPLORATION COMPANY

Existing 13-29-8-17 Pad
Proposed Well: 104-32-8-17
Sec. 29, T8S, R17E, S.L.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED:	10-14-14 A.P.C.
DATE:	09-10-2014		
VERSION:	V2		

COORDINATE REPORT

SHEET

1

RECEIVED: November 19, 2014



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 29 T8S, R17E
104-32-8-17**

Wellbore #1

Plan: Design #1

Standard Planning Report

09 September, 2014





Payzone Directional

Planning Report



Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well 104-32-8-17
Company:	NEWFIELD EXPLORATION	TVD Reference:	104-32-8-17 @ 5252.0usft (PLAN KB)
Project:	USGS Myton SW (UT)	MD Reference:	104-32-8-17 @ 5252.0usft (PLAN KB)
Site:	SECTION 29 T8S, R17E	North Reference:	True
Well:	104-32-8-17	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	SECTION 29 T8S, R17E, T8S R17E			
Site Position:		Northing:	7,204,529.47 usft	Latitude: 40° 5' 20.491 N
From:	Lat/Long	Easting:	2,051,570.99 usft	Longitude: 110° 1' 49.208 W
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence: 0.94 °

Well	104-32-8-17, SHL: 40° 5' 1.850 -110° 2' 13.010			
Well Position	+N/-S	-1,886.1 usft	Northing:	7,202,613.24 usft
	+E/-W	-1,849.9 usft	Easting:	2,049,752.33 usft
Position Uncertainty	0.0 usft	Wellhead Elevation:	5,252.0 usft	Ground Level: 5,241.0 usft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	9/9/2014	10.89	65.75	51,978

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	191.54

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,414.2	12.21	191.54	1,408.0	-84.7	-17.3	1.50	1.50	0.00	191.54	
5,187.5	12.21	191.54	5,096.0	-866.8	-177.0	0.00	0.00	0.00	0.00	104-32-8-17 TGT
6,409.2	12.21	191.54	6,290.0	-1,120.0	-228.7	0.00	0.00	0.00	0.00	



Payzone Directional

Planning Report



Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well 104-32-8-17
Company:	NEWFIELD EXPLORATION	TVD Reference:	104-32-8-17 @ 5252.0usft (PLAN KB)
Project:	USGS Myton SW (UT)	MD Reference:	104-32-8-17 @ 5252.0usft (PLAN KB)
Site:	SECTION 29 T8S, R17E	North Reference:	True
Well:	104-32-8-17	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	1.50	191.54	700.0	-1.3	-0.3	1.3	1.50	1.50	0.00
800.0	3.00	191.54	799.9	-5.1	-1.0	5.2	1.50	1.50	0.00
900.0	4.50	191.54	899.7	-11.5	-2.4	11.8	1.50	1.50	0.00
1,000.0	6.00	191.54	999.3	-20.5	-4.2	20.9	1.50	1.50	0.00
1,100.0	7.50	191.54	1,098.6	-32.0	-6.5	32.7	1.50	1.50	0.00
1,200.0	9.00	191.54	1,197.5	-46.1	-9.4	47.0	1.50	1.50	0.00
1,300.0	10.50	191.54	1,296.1	-62.7	-12.8	64.0	1.50	1.50	0.00
1,400.0	12.00	191.54	1,394.2	-81.8	-16.7	83.5	1.50	1.50	0.00
1,414.2	12.21	191.54	1,408.0	-84.7	-17.3	86.4	1.50	1.50	0.00
1,500.0	12.21	191.54	1,491.9	-102.5	-20.9	104.6	0.00	0.00	0.00
1,600.0	12.21	191.54	1,589.6	-123.2	-25.2	125.8	0.00	0.00	0.00
1,700.0	12.21	191.54	1,687.4	-143.9	-29.4	146.9	0.00	0.00	0.00
1,800.0	12.21	191.54	1,785.1	-164.7	-33.6	168.1	0.00	0.00	0.00
1,900.0	12.21	191.54	1,882.9	-185.4	-37.9	189.2	0.00	0.00	0.00
2,000.0	12.21	191.54	1,980.6	-206.1	-42.1	210.4	0.00	0.00	0.00
2,100.0	12.21	191.54	2,078.3	-226.8	-46.3	231.5	0.00	0.00	0.00
2,200.0	12.21	191.54	2,176.1	-247.6	-50.5	252.7	0.00	0.00	0.00
2,300.0	12.21	191.54	2,273.8	-268.3	-54.8	273.8	0.00	0.00	0.00
2,400.0	12.21	191.54	2,371.5	-289.0	-59.0	295.0	0.00	0.00	0.00
2,500.0	12.21	191.54	2,469.3	-309.8	-63.2	316.1	0.00	0.00	0.00
2,600.0	12.21	191.54	2,567.0	-330.5	-67.5	337.3	0.00	0.00	0.00
2,700.0	12.21	191.54	2,664.7	-351.2	-71.7	358.5	0.00	0.00	0.00
2,800.0	12.21	191.54	2,762.5	-371.9	-75.9	379.6	0.00	0.00	0.00
2,900.0	12.21	191.54	2,860.2	-392.7	-80.2	400.8	0.00	0.00	0.00
3,000.0	12.21	191.54	2,958.0	-413.4	-84.4	421.9	0.00	0.00	0.00
3,100.0	12.21	191.54	3,055.7	-434.1	-88.6	443.1	0.00	0.00	0.00
3,200.0	12.21	191.54	3,153.4	-454.8	-92.9	464.2	0.00	0.00	0.00
3,300.0	12.21	191.54	3,251.2	-475.6	-97.1	485.4	0.00	0.00	0.00
3,400.0	12.21	191.54	3,348.9	-496.3	-101.3	506.5	0.00	0.00	0.00
3,500.0	12.21	191.54	3,446.6	-517.0	-105.6	527.7	0.00	0.00	0.00
3,600.0	12.21	191.54	3,544.4	-537.7	-109.8	548.8	0.00	0.00	0.00
3,700.0	12.21	191.54	3,642.1	-558.5	-114.0	570.0	0.00	0.00	0.00
3,800.0	12.21	191.54	3,739.9	-579.2	-118.3	591.2	0.00	0.00	0.00
3,900.0	12.21	191.54	3,837.6	-599.9	-122.5	612.3	0.00	0.00	0.00
4,000.0	12.21	191.54	3,935.3	-620.7	-126.7	633.5	0.00	0.00	0.00
4,100.0	12.21	191.54	4,033.1	-641.4	-131.0	654.6	0.00	0.00	0.00
4,200.0	12.21	191.54	4,130.8	-662.1	-135.2	675.8	0.00	0.00	0.00
4,300.0	12.21	191.54	4,228.5	-682.8	-139.4	696.9	0.00	0.00	0.00
4,400.0	12.21	191.54	4,326.3	-703.6	-143.7	718.1	0.00	0.00	0.00
4,500.0	12.21	191.54	4,424.0	-724.3	-147.9	739.2	0.00	0.00	0.00
4,600.0	12.21	191.54	4,521.7	-745.0	-152.1	760.4	0.00	0.00	0.00
4,700.0	12.21	191.54	4,619.5	-765.7	-156.3	781.5	0.00	0.00	0.00
4,800.0	12.21	191.54	4,717.2	-786.5	-160.6	802.7	0.00	0.00	0.00
4,900.0	12.21	191.54	4,815.0	-807.2	-164.8	823.9	0.00	0.00	0.00
5,000.0	12.21	191.54	4,912.7	-827.9	-169.0	845.0	0.00	0.00	0.00
5,100.0	12.21	191.54	5,010.4	-848.7	-173.3	866.2	0.00	0.00	0.00
5,187.5	12.21	191.54	5,096.0	-866.8	-177.0	884.7	0.00	0.00	0.00



Payzone Directional Planning Report



Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well 104-32-8-17
Company:	NEWFIELD EXPLORATION	TVD Reference:	104-32-8-17 @ 5252.0usft (PLAN KB)
Project:	USGS Myton SW (UT)	MD Reference:	104-32-8-17 @ 5252.0usft (PLAN KB)
Site:	SECTION 29 T8S, R17E	North Reference:	True
Well:	104-32-8-17	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		



Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
5,200.0	12.21	191.54	5,108.2	-869.4	-177.5	887.3	0.00	0.00	0.00	
5,300.0	12.21	191.54	5,205.9	-890.1	-181.7	908.5	0.00	0.00	0.00	
5,400.0	12.21	191.54	5,303.6	-910.8	-186.0	929.6	0.00	0.00	0.00	
5,500.0	12.21	191.54	5,401.4	-931.6	-190.2	950.8	0.00	0.00	0.00	
5,600.0	12.21	191.54	5,499.1	-952.3	-194.4	971.9	0.00	0.00	0.00	
5,700.0	12.21	191.54	5,596.9	-973.0	-198.7	993.1	0.00	0.00	0.00	
5,800.0	12.21	191.54	5,694.6	-993.7	-202.9	1,014.2	0.00	0.00	0.00	
5,900.0	12.21	191.54	5,792.3	-1,014.5	-207.1	1,035.4	0.00	0.00	0.00	
6,000.0	12.21	191.54	5,890.1	-1,035.2	-211.4	1,056.5	0.00	0.00	0.00	
6,100.0	12.21	191.54	5,987.8	-1,055.9	-215.6	1,077.7	0.00	0.00	0.00	
6,200.0	12.21	191.54	6,085.5	-1,076.6	-219.8	1,098.9	0.00	0.00	0.00	
6,300.0	12.21	191.54	6,183.3	-1,097.4	-224.1	1,120.0	0.00	0.00	0.00	
6,409.2	12.21	191.54	6,290.0	-1,120.0	-228.7	1,143.1	0.00	0.00	0.00	

Design Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
104-32-8-17 TGT	0.00	0.00	5,096.0	-866.8	-177.0	7,201,743.67	2,049,589.55	40° 4' 53.283 N	110° 2' 15.287 W	
- hit/miss target										
- Shape										
- plan hits target center										
- Circle (radius 75.0)										



Project: USGS Myton SW (UT)
 Site: SECTION 29 T8S, R17E
 Well: 104-32-8-17
 Wellbore: Wellbore #1
 Design: Design #1

T M
 Azimuths to True North
 Magnetic North: 10.89°
 Magnetic Field
 Strength: 51977.6snT
 Dip Angle: 65.75°
 Date: 9/9/2014
 Model: IGRF2010



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
104-32-8-17 TGT	5096.0	-866.8	-177.0	Circle (Radius: 75.0)

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1414.2	12.21	191.54	1408.0	-84.7	-17.3	1.50	191.54	86.4	
4	5187.5	12.21	191.54	5096.0	-866.8	-177.0	0.00	0.00	884.7	104-32-8-17 TGT
5	6409.2	12.21	191.54	6290.0	-1120.0	-228.7	0.00	0.00	1143.1	



**NEWFIELD PRODUCTION COMPANY
GMBU 104-32-8-17
AT SURFACE: SW/SW SECTION 29, T8S R17E
DUCHESNE COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site GMBU 104-32-8-17 located in the SW 1/4 SW 1/4 Section 29, T8S, R17E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 – 1.4 miles \pm to the junction of this highway and UT State Hwy 53; proceed in a southeasterly direction – 8.2 miles \pm to it's junction with an existing road to the east; proceed in a easterly direction – 0.8 miles \pm to it's junction with the beginning of the access road to the existing 13-29-8-17 well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionaly off of the existing 13-29-8-17 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District
Water Right : 43-7478

Maurice Harvey Pond
Water Right: 47-1358

Neil Moon Pond
Water Right: 43-11787

Newfield Collector Well
Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

Fencing Requirements

- a) All pits will be fenced or have panels installed consistent with the following minimum standards:
 - 1. The wire shall be no more than two (2) inches above the ground. If barbed wire is utilized it will be installed three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
 - 2. Corner posts shall be centered and/or braced in such a manner to keep tight and upright at all times
 - 3. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

- a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

- b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP** – Bureau of Land Management.

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. MOAC Report # 14-316 11/5/14, prepared by Montgomery Archaeological Consultants. . Paleontological Resource Survey prepared by, SWCA Environmental Consultants, Report No. UT14-14273-182, October 2014. See attached report cover pages, Exhibit "D".

Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the GMBU 104-32-8-17, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the GMBU 104-32-8-17, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Name: Corie Miller
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #104-32-8-17, Section 29, Township 8S, Range 17E: Lease UTU-74869 Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #WYB000493.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

Date 11/18/14

Heather Calder
Regulatory Technician
Newfield Production Company


Typical 2M BOP stack configuration



2M CHOKE MANIFOLD EQUIPMENT - CONFIGURATION OF CHOKES MAY VARY

NEWFIELD EXPLORATION COMPANY**WELL PAD INTERFERENCE PLAT****EXISTING 13-29-8-17 PAD****PROPOSED WELL: 104-32-8-17**

Pad Location: SWSW (LOT 1) Section 32, T8S, R17E, S.L.B.&M.

**TOP HOLE FOOTAGES**

104-32-8-17
794' FSL & 813' FWL

**CENTER OF
PATTERN FOOTAGES**

104-32-8-17
69' FNL & 623' FWL

BOTTOM HOLE FOOTAGES

104-32-8-17
322' FNL & 567' FWL

LATITUDE & LONGITUDE
 Surface Position of Wells (NAD 83)

WELL	LATITUDE	LONGITUDE
13-29-8-17	40° 05' 01.67"	110° 02' 13.16"
104-32-8-17	40° 05' 01.85"	110° 02' 13.01"

RELATIVE COORDINATES
 From Top Hole to C.O.P.

WELL	NORTH	EAST
104-32-8-17	-867'	-177'

LATITUDE & LONGITUDE
 Center of Pattern (NAD 83)

WELL	LATITUDE	LONGITUDE
104-32-8-17	40° 04' 53.31"	110° 02' 15.47"

RELATIVE COORDINATES
 From Top Hole to Bottom Hole

WELL	NORTH	EAST
104-32-8-17	-1,120'	-229'

LATITUDE & LONGITUDE
 Bottom Hole Position (NAD 83)





WELL	LATITUDE	LONGITUDE
104-32-8-17	40° 04' 50.82"	110° 02' 16.19"

Note:
Bearings
are based
on GPS
Observations.

SURVEYED BY: S.H.	DATE SURVEYED: 09-04-14	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 09-08-14	V2
SCALE: 1" = 60'	REVISED: F.T.M. 10-14-14	

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: November 19, 2014

NEWFIELD EXPLORATION COMPANY***CROSS SECTIONS
EXISTING 13-29-8-17 PAD
PROPOSED WELL: 104-32-8-17****Pad Location: SWSW (LOT 1) Section 29, T8S, R17E, S.L.B.&M.*

NOTE:
UNLESS OTHERWISE NOTED ALL
CUT SLOPES ARE AT 1.1:1
FILL SLOPES ARE AT 1.5:1


ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	170	40	Topsoil is not included in Pad Cut	130
PIT	690	0		690
TOTALS	860	40	220	820

SURVEYED BY: S.H.	DATE SURVEYED: 09-04-14	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 09-08-14	V2
SCALE: 1" = 60'	REVISED: F.T.M. 10-14-14	

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501


RECEIVED: November 19, 2014

NEWFIELD EXPLORATION COMPANY**TYPICAL RIG LAYOUT****EXISTING 13-29-8-17 PAD****PROPOSED WELL: 104-32-8-17***Pad Location: SWSW (LOT 1) Section 29, T8S, R17E, S.L.B.&M.*

SURVEYED BY: S.H.	DATE SURVEYED: 09-04-14	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 09-08-14	V2
SCALE: 1" = 60'	REVISED: F.T.M. 10-14-14	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: November 19, 2014

NEWFIELD EXPLORATION COMPANY**RECLAMATION LAYOUT****EXISTING 13-29-8-17 PAD****PROPOSED WELL: 104-32-8-17***Pad Location: SWSW (LOT 1) Section 29, T8S, R17E, S.L.B.&M.***Notes:**

1. Reclaimed Area to Include Seeding of Approved Vegetation and Sufficient Storm Water Management System.
2. Actual Equipment Layout and Reclaimed Pad Surface Area May Change due to Production Requirements or Site Conditions.

DISTURBED AREA:

TOTAL DISTURBED AREA = ± 1.34 ACRES
 TOTAL RECLAIMED AREA = ± 0.88 ACRES
 UNRECLAIMED AREA = ± 0.46 ACRES


SURVEYED BY: S.H.	DATE SURVEYED: 09-04-14	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 09-08-14	V2
SCALE: 1" = 60'	REVISED: F.T.M. 10-14-14	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: November 19, 2014

NEWFIELD EXPLORATION COMPANY**PROPOSED SITE FACILITY DIAGRAM****13-29-8-17 PAD****104-32-8-17 UTU-74869**

*Pad Location: SWSW (LOT 1) Section 29, T8S, R17E, S.L.B.&M.
Duchesne County, Utah*

**Legend**


Emulsion Line
 Load Rack -----
 Water Line - - - - -
 Gas Sales - -
 Oil Line _____

NOT TO SCALE

SURVEYED BY: S.H.	DATE SURVEYED: 09-04-14	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 09-08-14	V2
SCALE: NONE	REVISED: F.T.M. 10-14-14	

Tri State (435) 781-2501
 Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: November 19, 2014



API Number: 4301353234



Well Name: GMBU 104-32-8-17

Township: T08.0S Range: R17.0E Section: 29 Meridian: S

Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared: 11/20/2014
Map Produced by Diana Mason

Wells Query	Units
Status	STATUS
APD - Approved Permit	ACTIVE
DRL - Spudded (Drilling Commenced)	EXPLORATORY
GRW - Gas Injection	GAS STORAGE
GS - Gas Storage	NF PP OIL
LOC - New Location	NF SECONDARY
OPS - Operation Suspended	PI OIL
PA - Plugged Abandoned	PP GAS
PGW - Producing Gas Well	PP GEOTHERMAL
POW - Producing Oil Well	PP OIL
SGW - Shut-in Gas Well	SECONDARY
SGW - Shut-in Oil Well	TERMINATED
TA - Temp. Abandoned	
TW - Test Well	
WOW - Water Disposal	
WW - Water Injection Well	
WSW - Water Supply Well	
	Fields
	STATUS
	Unknown
	ABANDONED
	ACTIVE
	COMBINED
	INACTIVE
	STORAGE
	TERMINATED



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
440 West 200 South, Suite 500
Salt Lake City, UT 84101

IN REPLY REFER TO:

3160
(UT-922)

November 24, 2014

Memorandum

To: Assistant Field Office Manager Minerals,
Vernal Field Office

From: Michael Coulthard, Petroleum Engineer

Subject: 2014 Plan of Development Greater Monument
Butte Unit, Duchesne and Uintah Counties,
Utah.

Pursuant to email between Diana Mason, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2014 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-53233	GMBU 110-31-8-17	Sec 31 T08S R17E 0819 FNL 2071 FEL BHL Sec 31 T08S R17E 1456 FNL 1920 FEL
43-013-53234	GMBU 104-32-8-17	Sec 29 T08S R17E 0794 FSL 0813 FWL BHL Sec 32 T08S R17E 0322 FNL 0567 FWL
43-013-53235	GMBU 117-31-8-17	Sec 31 T08S R17E 2025 FNL 0647 FEL BHL Sec 31 T08S R17E 2455 FSL 0641 FEL
43-013-53236	GMBU 109-31-8-17	Sec 31 T08S R17E 2005 FNL 0653 FEL BHL Sec 31 T08S R17E 1124 FNL 0639 FEL
43-047-54937	GMBU 110-36-8-17	Sec 36 T08S R17E 0772 FNL 2011 FEL BHL Sec 36 T08S R17E 1530 FNL 1989 FEL
43-047-54938	GMBU 13-36-8-17	Sec 36 T08S R17E 0706 FSL 0565 FWL
43-047-54983	GMBU K-14-9-17	Sec 13 T09S R17E 2121 FSL 0815 FWL BHL Sec 14 T09S R17E 2428 FNL 0259 FEL

This office has no objection to permitting the wells at this time.

Michael Coulthard

Digitally signed by Michael Coulthard
DN: cn=Michael Coulthard, o=Bureau of Land Management,
ou=Division of Minerals, email=mcoulth@blm.gov, c=US
Date: 2014.11.24 10:40:54 -0700

RECEIVED: November 25, 2014

API Well Number: 43013532340000

bcc: File - Greater Monument Butte Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron



MCoulthard:mc:11-24-14

RECEIVED: November 25, 2014



Project: USGS Myton SW (UT)
 Site: SECTION 31 T8S R17E
 Well: 110-31-8-17
 Wellbore: Wellbore #1
 Design: Design #1

T M
 Azimuths to True North
 Magnetic North: 10.90°
 Magnetic Field
 Strength: 51973.6snT
 Dip Angle: 65.74°
 Date: 9/9/2014
 Model: IGRF2010



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
110-31-8-17 TGT	5084.0	-496.2	125.6	Circle (Radius: 75.0)

SECTION DETAILS



Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VFace	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1057.3	6.86	165.80	1056.2	-26.5	6.7	1.50	165.80	27.3	
4	5114.1	6.86	165.80	5084.0	-496.2	125.6	0.00	0.00	511.9	110-31-8-17 TGT
5	6307.7	6.86	165.80	6269.0	-634.5	160.5	0.00	0.00	654.4	





Project: USGS Myton SW (UT)
 Site: SECTION 29 T8S, R17E
 Well: 104-32-8-17
 Wellbore: Wellbore #1
 Design: Design #1

T M
 Azimuths to True North
 Magnetic North: 10.89°
 Magnetic Field
 Strength: 51977.6snT
 Dip Angle: 65.75°
 Date: 9/9/2014
 Model: IGRF2010



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
104-32-8-17 TGT	5096.0	-866.8	-177.0	Circle (Radius: 75.0)

SECTION DETAILS



Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1414.2	12.21	191.54	1408.0	-84.7	-17.3	1.50	191.54	86.4	
4	5187.5	12.21	191.54	5096.0	-866.8	-177.0	0.00	0.00	884.7	104-32-8-17 TGT
5	6409.2	12.21	191.54	6290.0	-1120.0	-228.7	0.00	0.00	1143.1	





Project: USGS Myton SW (UT)
 Site: SECTION 31 T8S R17E
 Well: 117-31-8-17
 Wellbore: Wellbore #1
 Design: Design #1

T M Azimuths to True North
 Magnetic North: 10.90°
 Magnetic Field
 Strength: 51975.7snT
 Dip Angle: 65.74°
 Date: 8/27/2014
 Model: IGRF2010



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
117-31-8-17 TGT	5081.0	-635.2	15.0	Circle (Radius: 75.0)

SECTION DETAILS



Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VFace	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1174.4	8.62	178.65	1172.2	-43.1	1.0	1.50	178.65	43.1	
4	5127.8	8.62	178.65	5081.0	-635.2	15.0	0.00	0.00	635.4	117-31-8-17 TGT
5	6325.3	8.62	178.65	6265.0	-814.6	19.2	0.00	0.00	814.8	





Project: USGS Myton SW (UT)
 Site: SECTION 31 T8S R17E
 Well: 109-31-8-17
 Wellbore: Wellbore #1
 Design: Design #1

T M Azimuths to True North
 Magnetic North: 10.90°
 Magnetic Field
 Strength: 51975.8snT
 Dip Angle: 65.74°
 Date: 8/27/2014
 Model: IGRF2010



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
109-31-8-17 TGT	5072.0	684.6	-0.6	Circle (Radius: 75.0)

SECTION DETAILS



Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VFace	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1223.0	9.35	359.95	1220.3	50.7	0.0	1.50	359.95	50.7	
4	5126.6	9.35	359.95	5072.0	684.6	-0.6	0.00	0.00	684.6	109-31-8-17 TGT
5	6336.6	9.35	359.95	6266.0	881.1	-0.8	0.00	0.00	881.1	





Project: USGS Myton SW (UT)
 Site: SECTION 36 T8S, R17E
 Well: 110-36-8-17
 Wellbore: Wellbore #1
 Design: Design #1

T M
 Azimuths to True North
 Magnetic North: 10.86°
 Magnetic Field
 Strength: 51993.3snT
 Dip Angle: 65.76°
 Date: 8/22/2014
 Model: IGRF2010



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
110-36-8-17 TGT	5096.0	-593.6	26.6	Circle (Radius: 75.0)

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VFace	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1133.2	8.00	177.43	1131.4	-37.1	1.7	1.50	177.43	37.2	
4	5136.7	8.00	177.43	5096.0	-593.6	26.6	0.00	0.00	594.2	110-36-8-17 TGT
5	6320.2	8.00	177.43	6268.0	-758.1	34.0	0.00	0.00	758.8	



API Well Number: 43013532340000





Project: USGS Myton SW (UT)
 Site: Section 13 T 9S R17E
 Well: K-14-9-17
 Wellbore: Wellbore #1
 Design: Design #1



Azimuths to True North
 Magnetic North: 10.95°

Magnetic Field
 Strength: 52035.3snT
 Dip Angle: 65.74°
 Date: 12/2/2013
 Model: IGRF2010

KOP @ 600'
 DOGLEG RATE 1.5 DEG/100
 TARGET RADIUS IS 75'



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
K-14-9-17 TGT	4600.0	550.2	-825.3	Circle (Radius: 75.0)

Sec 1



SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.00	0.00	0.0	
3	1665.3	15.98	303.69	1651.6	81.9	-122.8	303.69	147.6	
4	4732.3	15.98	303.69	4600.0	550.2	-825.3	0.00	991.9	K-14-9-17 TGT
5	5876.5	15.98	303.69	5700.0	725.0	-1087.5	0.00	1307.0	

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 11/19/2014

API NO. ASSIGNED: 43013532340000

WELL NAME: GMBU 104-32-8-17

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4936

CONTACT: Heather Calder

PROPOSED LOCATION: SWSW 29 080S 170E

Permit Tech Review: ☒

SURFACE: 0794 FSL 0813 FWL

Engineering Review: ☐

BOTTOM: 0322 FNL 0567 FWL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.08386

LONGITUDE: -110.03687

UTM SURF EASTINGS: 582112.00

NORTHINGS: 4437509.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-74869

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 1 - Federal

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: FEDERAL - WYB000493☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 437478☐ RDCC Review:☐ Fee Surface Agreement☐ Intent to Commingle

Commingling Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit: GMBU (GRRV)

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: Cause 213-11

Effective Date: 11/30/2009

Siting: Suspends General Siting

☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 4 - Federal Approval - dmason
15 - Directional - dmason
27 - Other - bhill

RECEIVED: November 25, 2014



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: GMBU 104-32-8-17
API Well Number: 43013532340000
Lease Number: UTU-74869
Surface Owner: FEDERAL
Approval Date: 11/25/2014

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-74869
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: GMBU 104-32-8-17
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0794 FSL 0813 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 29 Township: 08.0S Range: 17.0E Meridian: S		9. API NUMBER: 43013532340000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/25/2015	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Newfield proposes to extend the Application for Permit to Drill this well.

Approved by the
 November 10, 2015
 Oil, Gas and Mining

Date: _____

By:

NAME (PLEASE PRINT) Mandie Crozier	PHONE NUMBER 435 646-4825	TITLE Regulatory Tech
SIGNATURE N/A	DATE 11/10/2015	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013532340000

API: 43013532340000

Well Name: GMBU 104-32-8-17

Location: 0794 FSL 0813 FWL QTR SWSW SEC 29 TWNP 080S RNG 170E MER S

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/25/2014

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 11/10/2015

Title: Regulatory Tech **Representing:** NEWFIELD PRODUCTION COMPANY

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-74869
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: GMBU 104-32-8-17
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0794 FSL 0813 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 29 Township: 08.0S Range: 17.0E Meridian: S		9. API NUMBER: 43013532340000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/25/2016 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Newfield proposes to extend the Application for Permit to Drill this well.		
<div style="color: red; font-weight: bold;"> Approved by the Commissioner of Oil, Gas and Mining </div> <div style="color: red; font-weight: bold;"> Date: _____ By: </div>		
NAME (PLEASE PRINT) Mandie Crozier		PHONE NUMBER 435 646-4825
SIGNATURE N/A		TITLE Regulatory Tech DATE 11/8/2016



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013532340000

API: 43013532340000

Well Name: GMBU 104-32-8-17

Location: 0794 FSL 0813 FWL QTR SWSW SEC 29 TWNP 080S RNG 170E MER S

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 11/25/2014

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Mandie Crozier

Date: 11/8/2016

Title: Regulatory Tech Representing: NEWFIELD PRODUCTION COMPANY